





# COASTAL DEMOLITION AS APPLIED TO MODIFICATIONS OF WINDOW OPENINGS




Sill of existing 3'x3' window is demolished to create a 3'x6' door does not result in demo




If an opening is framed in (either partially or completely) and the four planes of the window are left intact, then the entire width of the opening may be counted as remaining & not demolished.




King stud & trim of existing 3'x3' window demolished to create a 6'x3' window results in 3' of linear demo



Shifting an existing 3'x3' window 2' to the side by framing in 2' of the existing opening and demolishing the king stud & trim plus 2 linear feet of wall results in 2' of linear demo




Sill & king stud & trim of existing 3'x3' window is demolished to create a 6'x6' opening results in 3' of linear demo





Shifting an existing 9'x3' multi-part window under a common header 3' to the side by framing in one of the existing windows and demolishing the outer king stud & trim plus 3 linear feet of wall results in 3' of linear demo

**DRAFT**




- Definitions:**
- <sup>1</sup>Header: A framing member that supports the cut ends of studs or joists, usually over a window or door.
  - <sup>2</sup>Sill: Another name for sill plate; the bottom horizontal framing member of a window or door opening.
  - <sup>3</sup>King Stud: The outer, full-height studs on either side of a window or door opening.

# COASTAL DEMOLITION AS APPLIED TO OTHER WALL MODIFICATIONS



**DRAFT**




**PLEASE ALSO NOTE:**

- \* Walls to remain may not be shifted or moved in any way, even temporarily to accommodate foundation work or excavation. If the walls are shifted in any direction from their existing location, they are considered demolished for CDP exemption purposes. Walls must be suspended exactly in place for any foundation work or excavation activities.
- \* Once a 50% exemption project has been finalized by the building inspector, the completed project becomes the "existing" walls, and another project proposing up to 50% demolition of those walls may be approved. The requirement that "existing walls" be in place on or before March 17, 1990 was removed with the adoption of the LDC in 2000.

# DEMO SHEET EXAMPLE



**DRAFT**



## 1ST FLOOR DEMO PLAN

Scale 1/8" = 1'-0"


### DEMOLITION SYMBOL

- 2**  WALL REMOVAL PER DEFINITION OF CITY OF SAN DIEGO
-  NO CHANGE TO EXISTING EXTERIOR WALL

# 2ND FLOOR DEMO PLAN

Scale 1/8" = 1'-0"

# DRAFT



# 2ND FLOOR DEMO PLAN

Scale 1/8" = 1'-0"

## DEMOLITION SYMBOL

- WALL REMOVAL PER DEFINITION OF CITY OF SAN DIEGO
- NO CHANGE TO EXISTING EXTERIOR WALL

## WALL MATRIX

WALL NUMBER	EXISTING WALL LENGTH	REMOVED WALL LENGTH	REMAINING WALL LENGTH
1	22'-2"	NONE	22'-2"
2	29'-7"	4'-0"	25'-7"
3	31'-10"	23'-5"	8'-0"
4	24'-8"	8'-0"	16'-8"
5	49'-11"	41'-11"	8'-0"
6	53'-3"	15'-4"	38'-11"
7	22'-0"	19'-11"	2'-1"
8	34'-0"	24'-8"	9'-10"
9	22'-0"	15'-5"	2'-7"
10	37'-6"	4'-4"	33'-2"
TOTAL	322'-4"	189'-9"	33'-2"
54% OF ORIGINAL WALL LENGTH TO REMAIN			